

**TEST TITLE:** AN/SPQ-14 ASDS RACK ILO (LHD 7)

**TEST NO.:** 45011-3-062

**REV/CHG:** B

---

**COVER SHEET**

---

**TEST PROCEDURE PREPARATION:**

Prepared by: \_\_\_\_\_  
TDA Organization and Code

Date: \_\_\_\_\_

**TEST PROCEDURE REVIEW:**

Reviewed by: \_\_\_\_\_  
TDM Organization and Code

Date: \_\_\_\_\_

**DOCUMENTATION CERTIFICATION:**

Approved by: \_\_\_\_\_  
TDD Organization and Code

Date: \_\_\_\_\_

---

**REVISION RECORD**

---

<u>REV/CHG</u>	<u>DESCRIPTION</u>	Approval	
		<u>INITIAL</u>	<u>DATE</u>
-	Original Issue	FES	14 AUG 98
A	Incorporated shipyard changes.	FES	18 DEC 98
B	Incorporates TPR 7207-086-C dtd. 07/01/99	FES	06 JAN 00

---

**LIST OF EFFECTIVE PAGES**

---

<u>PG-REV</u>	<u>PG-REV</u>	<u>PG-REV</u>	<u>PG-REV</u>	<u>PG-REV</u>	<u>PG-REV</u>	<u>PG-REV</u>
1 - B	2 - B	3 - B	4 - B	5 - B	6 - B	7 - B
8 - B	9 - B	10 - B	11 - B	12 - B	13 - B	14 - B
15 - B	16 - B	17 - B	18 - B	19 - B	20 - B	21 - B
22 - B	23 - B	24 - B	25 - B	26 - B	27 - B	28 - B
29 - B	30 - B	31 - B	32 - B	33 - B	34 - B	35 - B
36 - B						

---

**TEST OUTLINE**

---

1. OBJECTIVE:

To verify that the SB-4229A(V)11/SP Radar Signal Distribution Switchboard (SB-4229A(V)11/SP RSDS) installed within a MT-7085/U Electrical Equipment Rack (MT-7085/U Rack) provides power distribution and is operating properly during initial light-off.

2. ESTIMATED TESTING TIME:

4 hours

3. REFERENCES:

SE245-AE-MMO-A10, Technical Manual, for the Radar Signal Distribution Switchboard SB-4229A(V)11/SP

4. TEST OR SUPPORT EQUIPMENT AND MATERIAL:

<u>GENERIC NAME</u>	<u>QUANTITY</u>	<u>IDENTIFYING INFORMATION</u>
a. Frequency Counter	1	SCAT 4296 or equivalent
b. Multimeter, Digital	1	SCAT 4237 or equivalent

5. COMPUTER PROGRAMS REQUIRED:

None

6. PREREQUISITES:

32011-2-001 Power Distribution System Insulation Resistance Test

7. SPECIAL CONDITIONS AND SERVICES:

115 VAC, 1  $\phi$ , 60 Hz Power

8. EQUIPMENT INVOLVED IN TEST:

- a. CD-135/U, Controller, Tracking Data (CD-135/U Controller) (Optional Equipment installed by Engineering Change, EC-6)
- b. MT-7085/U Rack
- c. RD-670/U, Recorder-Reproducer (RD-670/U RADCOR) (Optional Equipment installed by EC-9)
- d. SB-4229A(V)11/SP RSDS
- e. SM-902/U, Simulator, Video Signal (SM-902/U VSS) (Optional Equipment installed by EC-8)

---

**TEST OUTLINE**


---

9. CONFIGURATION:

<u>EQUIPMENT</u>	<u>NOMENCLATURE</u>	<u>ALLOWANCE PARTS LIST (APL)</u>
a. SB-4229A(V)11/SP W/EC1	SB-4229A(V)11/SP RSDS with EC-1	00037332
b. SB-4229A(V)11/SP EC6	SB-4229A(V)11/SP RSDS with EC-6	00037375
c. SB-4229A(V)11/SP EC8	SB-4229A(V)11/SP RSDS with EC-8	00037377
d. SB-4229A(V)11/SP EC9	SB-4229A(V)11/SP RSDS with EC-9	00037378
e. MT-7085/U	MT-7085/U Rack installed by EC-1	00036958
f. CD-135/U	CD-135/U Controller installed by EC-6	00036956
g. SM-902/U	SM-902/U VSS installed by EC-8	00036957
h. RD-670/U	RD-670/U RADCOR installed by EC-9	00036959

10. METHOD:

A visual inspection of the equipment will be conducted to ensure that it is free of damage, debris and loose wire connections. Ensure input and power supply voltage levels are within tolerance. Verify that indicator lamps are lit for specified equipment.

11. STATION ASSIGNMENTS:

<u>STATION</u>	<u>NO. PERSONNEL</u>	<u>COMMENTS</u>
SB-4229A(V)11/SP RSDS	2 Electronic Technicians	Performs ILO Test

---

**SAFETY INSTRUCTIONS**

---

- a. The operation of this equipment involves the use of high voltages that are dangerous to life. Extreme caution must be exercised at all times. Do not work on open or disassembled units when power is applied.
- b. Turning OFF the MT-7085/U Rack Power Distribution Unit (PDU) by using the power circuit breaker or switch does not remove the ship 115 VAC.
- c. MT-7085/U Racks containing an Uninterruptible Power Source (UPS) may retain 115 VAC on UPS associated equipment when power is removed from the MT-7085/U Rack or the UPS circuit breaker is in the OFF position.

---

**INITIAL CONDITIONS AND SETUP**


---

<b><u>STEP</u></b>	<b><u>STATION</u></b>	<b><u>INSTRUCTIONS</u></b>
1	SPDP	Turn OFF and tag Main Circuit Breaker at Ship Power Distribution Panel (SPDP).
2	MT-7085/U Rack	Open the equipment enclosure's front door.
3	MT-7085/U Rack	Inspect equipment for: Presence of foreign matter. Loose cables and cable connections. Damaged or chaffed cable insulation. Loose or missing protective covers. Loose modules, fastening hardware or circuit cards

**NOTE**

This procedure is written in a manner that addresses the SB-4229A(V)11/SP RSDS EC's that can be installed within the MT-7085/U Rack. The equipment and test steps that apply are listed below. Omit test steps for hardware that is not installed.

**Equipment**  
 SB-4229A(V)11/SP RSDS  
 MT-7085/U Rack  
  
 CD-135/U Controller  
 SM-902/U VSS  
 RD-670/U RADCOR

**Test Steps**  
 9-14  
 1, 2, 4, 6, 8, 15-17, 24, 28, 30-32  
 29, 33-41  
 18-23  
 25-27

4	MT-7085/U Rack	<p>Set the following switches and breakers to OFF position (See Figure 1A or 1B):</p> <ol style="list-style-type: none"> <li>Power switch on CD-135/U Controller 748i computer is not depressed.</li> <li>OUTPUT switch on CD-135/U Controller UPS.</li> <li>INPUT switch on CD-135/U Controller UPS.</li> <li>AC POWER switch on SM-902/U VSS.</li> <li>Power switch on RD-670/U RADCOR Recorder.</li> <li>Power Supply module switches of both the Upper and Lower SB-4229A(V)11/SP RSDS chassis.</li> </ol>
---	----------------	--

---

**INITIAL CONDITIONS AND SETUP**


---

**STEP    STATION****INSTRUCTIONS**

- g) AC PWR switch on both the Upper and Lower SB-4229A(V)11/ RSDS Master Control Panel.
- h) AUX. switch on PDU.
- i) SWITCHER switch on PDU.
- j) RADCOR switch on PDU.
- k) VSS switch on PDU.
- l) MAIN POWER, CB3 circuit breaker on PDU.
- m) SWITCH BD POWER, CB2 circuit breaker on PDU.
- n) UPS POWER, CB1 circuit breaker on PDU.

**CAUTION**

Switchboard modules are Electrostatic Discharge Sensitive (ESD). Observe ESD precautions while handling.

5        SB-4229A(V)11/SP  
RSDS

Loosen fasteners and remove the Controller module from the SB-4229A(V)11/SP RSDS Upper chassis. (See Figure 1A or 1B) Set the Controller module internal and front panel switches. (See Figures 2 and 3).

**NOTE**

Figures of dip switches shaded in black are shown in the set position.

Internal switches: S9, S10, S11, S12, S13, S14, S15, and S16 as shown in Figure 2.

Set Panel switches as shown in Figure 3:

Input 10  
Input 1  
Output 10  
Output 1  
LCL/RMT 1-8  
LCL/RMT 9-16  
LCL/RMT 17-24

6        SB-4229A(V)11/SP RSDS

Reinstall the Controller module securing fasteners.

---

**INITIAL CONDITIONS AND SETUP**

---

<b><u>STEP</u></b>	<b><u>STATION</u></b>	<b><u>INSTRUCTIONS</u></b>
7	SB-4229A(V)11/SP RSDS	Loosen fasteners and remove Configuration module from the SB-4229A(V)11/SP RSDS Upper chassis. (See Figure 1A or 1B). Set Configuration module internal switches (See Figure 4).  Set Internal switches as shown in Figure 4: S1, S2, S3, S4, S5, S6, S7, S8, S9, S10, S11, S12, S13, S14, S15, S16, S17, S18, S19, S20, S21, S22, S23, S24.
8	SB-4229A(V)11/SP RSDS	Reinstall Configuration module securing fasteners.
9		Repeat steps 5 thru 8 for the Controller and Configuration modules located in SB-4229A(V)11/SP RSDS Lower chassis (See Figure 1A or 1B).
10		Repeat steps 1-9 on second SB-4229A(V)11/SP RSDS Rack. Perform steps as required based on the equipment installed in the MT-7085/U Rack.



## INITIAL CONDITIONS AND SETUP




Figure 1A. SB-4229A(V)11/SP RSDS

## INITIAL CONDITIONS AND SETUP




Figure 1B. SB-4229A(V)11/SP RSDS

# INITIAL CONDITIONS AND SETUP




Figure 2. Upper and Lower Controller Module Switch Settings

---

**INITIAL CONDITIONS AND SETUP**


---




Figure 3. Upper and Lower Controller Module Front Panel Switch Settings




Figure 4. Upper And Lower Configuration Module Switch Settings

---

**TESTING STEPS**


---

**STEP**   **STATION****INSTRUCTIONS**NOTE

This ILO procedure includes steps that encompass all of the SB-4229A(V)11/SP RSDS Rack mounted equipment. Certain steps will be required to be repeated to accomplish ILO for both SB-4229A(V)11/SP RSDS Rack. There are separate Data Recording Sheets for each SB-4229A(V)11/SP RSDS Rack. Complete each of the Test Data Recording sheets as applicable. Additionally, test steps should only be performed for those equipment options that are installed. Steps that do not apply due to equipment being located in a separate SB-4229A(V)11/SP RSDS Rack or equipment options that are not installed should be completed with "N/A".

1      MT-7085/U Rack

Disconnect AC Input cable to J199 connector on the enclosure rear panel.

2      SPDP

Remove tag and turn ON Main Circuit Breaker at SPDP.

3      MT-7085/U Rack

Verify the following cable voltages and frequency:

ContactSignal Designation

A to C

105 VAC to 125 VAC

B to Chassis Ground &lt; 1 VAC

A to C

≥50 to ≤63 Hz

RECORD on Test Data Recording sheet.

4      SPDP

Turn OFF and tag Main Circuit Breaker at SPDP.

---

**TESTING STEPS**


---

<u>STEP</u>	<u>STATION</u>	<u>INSTRUCTIONS</u>										
5	MT-7085/U Rack	Reconnect AC Input cable to J199.										
6	SPDP	Remove tag and turn ON Main Circuit Breaker at SPDP.										
7	MT-7085/U Rack PDU	Turn ON CB2, SWITCH BD POWER circuit breaker. Observe CB2 indicator is Lit. <u>RECORD</u> on Test Data Recording sheet.										
8	SB-4229A(V)11/SP RSDS	Turn ON:  (a) AC PWR switch above Upper and Lower chassis. (b) Individual Power Supply module switches for both power supplies in Upper and Lower chassis.  Observe indicators are lit. <u>RECORD</u> on Test Data Recording sheet.										
9	SB-4229A(V)11/SP RSDS	Observe front panel LEDs on Power Supply module 1 and 2 are lit. (See Figure 5). <u>RECORD</u> on Test Data Recording sheet.										
10	SB-4229A(V)11/SP RSDS	Observe front panel CONT and PWR LED's are lit on all chassis modules excluding Power Supply modules. <u>RECORD</u> on Test Data Recording sheet.										
11	SB-4229A(V)11/SP RSDS	Turn OFF Power Supply module 2 (PS2) switch on both the Upper and Lower chassis and use a Digital Multimeter to monitor voltages at test points located on the front panel of Power Supply module 1 (PS1). Expected voltages and acceptable tolerances are as follows.  <table><tr><td><u>Test Point</u></td><td><u>Expected Value</u></td></tr><tr><td>+5V</td><td>+4.87 VDC to +5.39 VDC</td></tr><tr><td>-5V</td><td>-4.87 VDC to -5.39 VDC</td></tr><tr><td>+15V</td><td>+13.24 VDC to +14.64 VDC</td></tr><tr><td>-15V</td><td>-13.24 VDC to -14.64 VDC</td></tr></table>	<u>Test Point</u>	<u>Expected Value</u>	+5V	+4.87 VDC to +5.39 VDC	-5V	-4.87 VDC to -5.39 VDC	+15V	+13.24 VDC to +14.64 VDC	-15V	-13.24 VDC to -14.64 VDC
<u>Test Point</u>	<u>Expected Value</u>											
+5V	+4.87 VDC to +5.39 VDC											
-5V	-4.87 VDC to -5.39 VDC											
+15V	+13.24 VDC to +14.64 VDC											
-15V	-13.24 VDC to -14.64 VDC											

---

**TESTING STEPS**


---




Figure 5. Power Supply Module

**STEP    STATION****INSTRUCTIONS****NOTE**

Connect the common black lead to a ground (GND) test point and measure the test points indicated.

**NOTE**

Test voltages are  $\pm 13.5V$  not  $\pm 15V$  as marked on the Power Supply module front panels.

RECORD on Test Data Recording sheet.

12      SB-4229A(V)11/SP RSDS

Repeat the measurements of step 11 on the front panel test points for PS2 with PS2 ON and PS1 OFF for both Upper and Lower chassis. RECORD on Test Data Recording sheet.

---

**TESTING STEPS**


---

<b><u>STEP</u></b>	<b><u>STATION</u></b>	<b><u>INSTRUCTIONS</u></b>
13	SB-4229A(V)11/SP RSDS	Turn ON PS1 for both Upper and Lower chassis and disconnect Digital Multimeter test leads from Power Supply module.
<p style="text-align: center;"><b><u>NOTE</u></b></p> <p>The following test steps are for optional equipment that may be installed in the SB-4229A(V)11/SP RSDS Rack. Perform required test steps in accordance with the equipment configuration.</p>		
14	MT-7085/U Rack PDU	Turn ON MAIN POWER (CB3) circuit breaker and ensure indicator is lit. <b><u>RECORD</u></b> on Test Data Recording sheet.
15	MT-7085/U Rack PDU	Ensure FANS Indicator is lit and both fans located on top of MT-7085/U Rack are exhausting air. <b><u>RECORD</u></b> on Test Data Recording sheet.
16	MT-7085/U Rack PDU	Turn ON VSS (S1) switch and ensure indicator is lit. <b><u>RECORD</u></b> on Test Data Recording sheet.
*17	SM-902/U VSS	Remove and store 8 cup-head screws from front panel. Pull handles to extend SM-902/U VSS unit on slides to allow access to top cover panel.
<p style="text-align: center;"><b><u>CAUTION</u></b></p> <p>DO NOT remove the 6 Phillips head screws that span across middle of top cover.</p>		
*18	SM-902/U VSS	Remove and store cover panel with fastening hardware. To prevent captive screws from galling and binding, loosen 10 outer screws evenly around top perimeter.
*19	SM-902/U VSS	Turn ON AC POWER switch and ensure ON lamp is lit. <b><u>RECORD</u></b> on Test Data Recording sheet.

---

\* Step not applicable if equipment is not part of the SB-4229A(V)11/SP RSDS Configuration.



---

**TESTING STEPS**


---

<b><u>STEP</u></b>	<b><u>STATION</u></b>	<b><u>INSTRUCTIONS</u></b>																																																																														
*20	SM-902/U VSS	<p>Ensure the following LEDs on circuit card assembly front panels meet the following conditions.</p> <p>a) Slot 1A1</p> <table> <tr> <td>P-FAIL</td><td>ON</td><td>(Green)</td></tr> <tr> <td>B-BUSY</td><td>OFF</td><td></td></tr> <tr> <td>BERR</td><td>OFF</td><td></td></tr> </table> <p>b) Slot 1A2</p> <table> <tr> <td>RUN</td><td>ON</td><td>(Green)</td></tr> </table> <p>c) RADDs Slots 1A5 and 1A11</p> <table> <tr> <td>SIM</td><td>ON</td><td></td></tr> <tr> <td>TM</td><td>ON</td><td></td></tr> <tr> <td>TE</td><td>ON</td><td></td></tr> <tr> <td>TMT</td><td>ON</td><td></td></tr> <tr> <td>RADDs OUT</td><td>ON</td><td></td></tr> <tr> <td>AIR</td><td>OFF</td><td></td></tr> <tr> <td>SUR</td><td>OFF</td><td></td></tr> </table> <p>d) TARGET Slots 1A6 and 1A12</p> <table> <tr> <td>SIM</td><td>ON</td><td></td></tr> <tr> <td>TM</td><td>ON</td><td></td></tr> <tr> <td>TE</td><td>ON</td><td></td></tr> <tr> <td>TMT</td><td>ON</td><td></td></tr> <tr> <td>LIVE IN</td><td>OFF</td><td></td></tr> <tr> <td>LAND IN</td><td>OFF</td><td></td></tr> <tr> <td>TARG OUT</td><td>OFF</td><td></td></tr> </table> <p>e) IFF Slots 1A7 and 1A13</p> <table> <tr> <td>SIM</td><td>ON</td><td></td></tr> <tr> <td>TM</td><td>ON</td><td></td></tr> <tr> <td>TE</td><td>ON</td><td></td></tr> <tr> <td>TMT</td><td>ON</td><td></td></tr> <tr> <td>MTC IN</td><td>OFF</td><td></td></tr> <tr> <td>TR IN</td><td>OFF</td><td></td></tr> <tr> <td>MTC OUT</td><td>OFF</td><td></td></tr> <tr> <td>TR OUT</td><td>OFF</td><td></td></tr> </table> <p><u>RECORD</u> on Test Data Recording sheet.</p>	P-FAIL	ON	(Green)	B-BUSY	OFF		BERR	OFF		RUN	ON	(Green)	SIM	ON		TM	ON		TE	ON		TMT	ON		RADDs OUT	ON		AIR	OFF		SUR	OFF		SIM	ON		TM	ON		TE	ON		TMT	ON		LIVE IN	OFF		LAND IN	OFF		TARG OUT	OFF		SIM	ON		TM	ON		TE	ON		TMT	ON		MTC IN	OFF		TR IN	OFF		MTC OUT	OFF		TR OUT	OFF	
P-FAIL	ON	(Green)																																																																														
B-BUSY	OFF																																																																															
BERR	OFF																																																																															
RUN	ON	(Green)																																																																														
SIM	ON																																																																															
TM	ON																																																																															
TE	ON																																																																															
TMT	ON																																																																															
RADDs OUT	ON																																																																															
AIR	OFF																																																																															
SUR	OFF																																																																															
SIM	ON																																																																															
TM	ON																																																																															
TE	ON																																																																															
TMT	ON																																																																															
LIVE IN	OFF																																																																															
LAND IN	OFF																																																																															
TARG OUT	OFF																																																																															
SIM	ON																																																																															
TM	ON																																																																															
TE	ON																																																																															
TMT	ON																																																																															
MTC IN	OFF																																																																															
TR IN	OFF																																																																															
MTC OUT	OFF																																																																															
TR OUT	OFF																																																																															

---

\* Step not applicable if equipment is not part of the SB-4229A(V)11/SP RSDS Configuration.

---

**TESTING STEPS**


---

<u>STEP</u>	<u>STATION</u>	<u>INSTRUCTIONS</u>										
*21	SM-902/U VSS	Replace cover panel and push on handles to insert the chassis into enclosure. To prevent captive screws from galling and binding, tighten each screw evenly around top perimeter.										
*22	SM-902/U VSS	Reinstall unit into enclosure and replace the 8 cuphead screws on front panel.										
23	MT-7085/U Rack PDU	Turn ON the RADCOR (S2) switch and ensure indicator is lit. <u>RECORD</u> on Test Data Recording sheet.										
*24	RD-670/U RADCOR Witness	Ensure Witness Indicator/Display are as follows upon completion of unit's self-test. <table><tr><td><u>Indicator/Display</u></td><td><u>Status</u></td></tr><tr><td>Power</td><td>Indicator lit Green</td></tr><tr><td>Health INPUT</td><td>Indicator lit Red</td></tr><tr><td>Health OUTPUT</td><td>Indicator lit Green</td></tr><tr><td>DSQM LCD Display</td><td>Displays "TRIGGER INPUT SLOT 7 FAILED"</td></tr></table> <u>RECORD</u> on Test Data Recording sheet.	<u>Indicator/Display</u>	<u>Status</u>	Power	Indicator lit Green	Health INPUT	Indicator lit Red	Health OUTPUT	Indicator lit Green	DSQM LCD Display	Displays "TRIGGER INPUT SLOT 7 FAILED"
<u>Indicator/Display</u>	<u>Status</u>											
Power	Indicator lit Green											
Health INPUT	Indicator lit Red											
Health OUTPUT	Indicator lit Green											
DSQM LCD Display	Displays "TRIGGER INPUT SLOT 7 FAILED"											
*25	RD-670/U RADCOR Recorder	Set Power switch to ON.										
*26	RD-670/U RADCOR Recorder	Ensure EJECT button, AUDIO LEVEL meters, and Time counter display are lit. <u>RECORD</u> on Test Data Recording sheet.										
27	MT-7085/U Rack PDU	Turn ON SWITCHER (S3) switch and ensure indicator is lit. <u>RECORD</u> on Test Data Recording sheet.										
*28	CD-135/U Controller Switcher	Ensure Power ON Indicator is lit. <u>RECORD</u> on Test Data Recording sheet.										
29	MT-7085/U Rack PDU	Turn ON AUX (S4) switch and ensure indicator is lit. <u>RECORD</u> on Test Data Recording sheet.										

---

\* Step not applicable if equipment is not part of the SB-4229A(V)11/SP RSDS Configuration.

---

**TESTING STEPS**


---

<b><u>STEP</u></b>	<b><u>STATION</u></b>	<b><u>INSTRUCTIONS</u></b>
30	MT-7085/U Rack PDU	Turn OFF AUX (S4) switch and ensure indicator is extinguished. <u>RECORD</u> on Test Data Recording sheet.
31	MT-7085/U Rack PDU	Turn ON UPS POWER (CB1) circuit breaker and ensure indicator is Lit. <u>RECORD</u> on Test Data Recording sheet.
*32	CD-135/U Controller UPS	Turn ON INPUT POWER switch and ensure OK indicator is lit and BATTERY CHARGE % LEDs indicate 100%. <u>RECORD</u> on Test Data Recording sheet.
*33	CD-135/U Controller UPS	Turn ON OUTPUT POWER switch and ensure OK indicator is lit. <u>RECORD</u> on Test Data Recording sheet.
*34	CD-135/U Controller NetExpander	Remove front panel and ensure NetExpander Power switch is ON. Replace front panel.
*35	CD-135/U Controller HMI Drawer	Loosen 2 front panel captive screws then pull handles to extend HMI drawer on slides. Turn ON monitor by tilting monitor's viewing angle upwards from the horizontal position.
*36	CD-135/U Controller 748i Computer	Remove and store 4 cup-head screws from front panel. Pull handles to extend the 748i Computer on slides and ensure both rear Power Supply switches are ON.
*37	CD-135/U Controller 748i Computer	Push handles to retract the 748i Computer on slides and fasten. Replace 4 front panel cup-head screws.
*38	CD-135/U Controller 748i Computer	Set Power switch to ON and ensure power indicator is lit. Proceed immediately to next step to monitor system initialization. <u>RECORD</u> on Test Data Recording sheet.

---

\* Step not applicable if equipment is not part of the SB-4229A(V)11/SP RSDS Configuration.

---

**TESTING STEPS**

---

<b><u>STEP</u></b>	<b><u>STATION</u></b>	<b><u>INSTRUCTIONS</u></b>
*39	CD-135/U Controller HMI Drawer	Observe system initialization on video monitor and ensure the following are displayed:  Initializing System OK Starting Networking OK Starting System Functions OK Starting Diagnostics OK Starting Auditing OK <u>RECORD</u> on Test Data Recording sheet.
*40	CD-135/U Controller HMI Drawer	Ensure Login Window is displayed.
41		Repeat steps 1-40 on second SB-4229A(V)11/SP RSDS Rack. Perform steps as required based on optional equipment installed within MT-7085/U Rack.

---

\* Step not applicable if equipment is not part of the SB-4229A(V)11/SP Configuration.

---

**SHUTDOWN AND SECURING**


---

<b><u>STEP</u></b>	<b><u>STATION</u></b>	<b><u>INSTRUCTIONS</u></b>
*1	CD-135/U Controller HMI Drawer	Enter Login "shutdown" followed by the ENTER key.
*2	CD-135/U Controller HMI Drawer	Verify "Halted, you may now cycle power" message. (The Halt System process takes approximately 1 minute for Halt message to appear.)
3	SB-4229A(V)11/SP RSDS	Turn OFF.  (a) Individual Power Supply module switches for both power supplies in Upper and Lower chassis. (b) AC PWR switch above Upper and Lower chassis.
4	MT-7085/U Rack PDU	Set CB2, SWITCHBD POWER circuit breaker to OFF position.
*5	CD-135/U Controller 748i Computer	Set 748i Computer power switch to OFF and verify power indicator is extinguished.
*6	CD-135/U Controller UPS	Set UPS OUTPUT Power switch to OFF position and verify output indicator is extinguished.
*7	CD-135/U Controller UPS	Set UPS INPUT Power switch to OFF position and verify input indicator is extinguished.
8	MT-7085/U Rack PDU	Set UPS (CB1) circuit breaker to OFF position and verify indicator is extinguished.
9	MT-7085/U Rack PDU	Set SWITCHER (S3) switch to OFF position and verify indicator is extinguished.
*10	RS-670/U RADCOR Recorder	Set Power switch to OFF position and verify EJECT button, AUDIO LEVEL meters and Time counter displays are extinguished.
11	MT-7085/U Rack PDU	Set RADCOR (S2) switch to OFF position and verify indicator is extinguished.

---

\* Step not applicable if equipment is not part of the SB-4229A(V)11/SP Configuration.

---

**SHUTDOWN AND SECURING**

---

<b><u>STEP</u></b>	<b><u>STATION</u></b>	<b><u>INSTRUCTIONS</u></b>
*12	SM-902/U VSS	Set AC Power switch to OFF position and verify power indicator is extinguished.
13	MT-7085/U Rack PDU	Set VSS (S1) switch to OFF position and verify indicator is extinguished.
14	MT-7085/U Rack PDU	Set MAIN POWER (CB3) circuit breaker switch to OFF position and verify indicator is extinguished.
15	MT-7085/U Rack	Close MT-7085/U Rack front door.
16		Repeat steps 1-15 on second SB-4229(V)11/SP RSDS Rack. Perform steps as required based on the equipment installed in the MT-7085/U Rack.

---

\* Step not applicable if equipment is not part of the SB-4229A(V)11/SP Configuration.

---

**TEST DATA RECORDING**


---

**EQUIPMENT UNDER TEST**

<b><u>EQUIPMENT</u></b>	<b><u>SERIAL NO.</u></b>
SB-4229A(V)11/SP RSDS	_____
MT-7085/U Rack	_____
CD-135/U Controller	_____
SM-902/U VSS	_____
RD-670/U RADCOR	_____

**PREREQUISITES**

32011-2-001 Power Distribution System Insulation Resistance Test

**NOTE**

Write "N/A" in ACTUAL RESULTS spaces for test sections where optional equipment is not present in the SB-4229A(V)11/SP RSDS under test.

**TEST DATA RECORDING**

<b><u>STEP</u></b>	<b><u>TEST ELEMENT</u></b>	<b><u>EXPECTED RESULTS</u></b>	<b><u>ACTUAL RESULTS</u></b>
3	J199 <u>CONTACT</u>		
	A to C	105 VAC to 125 VAC	_____ VAC
	B to Chassis Ground	< 1 VAC	_____ VAC
	A to C	≥50 to ≤63 Hz	_____ Hz
7	PDU's <u>SWITCHBOARD INDICATOR IS LIT</u>		
	SWITCH BD (CB2) circuit breaker	Indicator is Lit	_____
8 (a)	<u>MASTER CONTROL PANEL'S INDICATOR IS LIT</u>		
	AC PWR switch and DC PWR indicator is lit for Upper chassis		_____
	AC PWR switch and DC PWR indicator is lit for Lower chassis		_____

SHIP HULL NO.

TEST CONDUCTOR  
SIGNATUREGOVERNMENT WITNESS  
SIGNATURE

DATE





---

**TEST DATA RECORDING**


---

<b><u>STEP</u></b>	<b><u>TEST ELEMENT</u></b>	<b><u>EXPECTED RESULTS</u></b>	<b><u>ACTUAL RESULTS</u></b>
11	<u>POWER SUPPLY TEST POINT VOLTAGES</u>		
	<u>PS1 for Upper chassis</u>		
	+5V	+4.87 VDC to +5.39 VDC	_____ VDC
	-5V	-4.87 VDC to -5.39 VDC	_____ VDC
	+15V	+13.24 VDC to +14.64 VDC	_____ VDC
	-15V	-13.24 VDC to -14.64 VDC	_____ VDC
	<u>PS1 for Lower chassis</u>		
	+5V	+4.87 VDC to +5.39 VDC	_____ VDC
	-5V	-4.87 VDC to -5.39 VDC	_____ VDC
	+15V	+13.24 VDC to +14.64 VDC	_____ VDC
	-15V	-13.24 VDC to -14.64 VDC	_____ VDC
12	<u>POWER SUPPLY TEST POINT VOLTAGES</u>		
	<u>PS2 for Upper chassis</u>		
	+5V	+4.87 VDC to +5.39 VDC	_____ VDC
	-5V	-4.87 VDC to -5.39 VDC	_____ VDC
	+15V	+13.24 VDC to +14.64 VDC	_____ VDC
	-15V	-13.24 VDC to -14.64 VDC	_____ VDC
	<u>PS2 for Lower chassis</u>		
	+5V	+4.87 VDC to +5.39 VDC	_____ VDC
	-5V	-4.87 VDC to -5.39 VDC	_____ VDC
	+15V	+13.24 VDC to +14.64 VDC	_____ VDC
	-15V	-13.24 VDC to -14.64 VDC	_____ VDC
14	<u>MAIN POWER PDU INDICATOR IS LIT</u>		
	MAIN POWER (CB3) circuit breaker	Indicator is Lit	_____
15	<u>FAN POWER PDU INDICATOR IS LIT AND FANS ROTATE</u>		
	MAIN POWER (CB3) circuit breaker	Fans Indicator is Lit	_____
		Fans Rotate	_____
16	<u>VSS INDICATOR IS LIT ON PDU</u>		
	VSS PDU switch	Indicator is Lit	_____
<hr/>			
SHIP HULL NO.	TEST CONDUCTOR SIGNATURE	GOVERNMENT WITNESS SIGNATURE	DATE
<hr/>			

---

**TEST DATA RECORDING**


---

<u>STEP</u>	<u>TEST ELEMENT</u>	<u>EXPECTED RESULTS</u>	<u>ACTUAL RESULTS</u>
19	<u>SM-902/U VSS POWER INDICATOR IS LIT</u> SM-902/U VSS AC POWER switch	Indicator is Lit	_____
20	<u>SM-902/U VSS CIRCUIT CARD FRONT PANEL LEDs</u>		
	<u>a) Slot 1A1</u>		
	P-FAIL	ON (Green)	_____
	B-BUSY	OFF	_____
	BERR	OFF	_____
	<u>b) Slot 1A2</u>		
	RUN	ON (Green)	_____
	<u>c) RADDs Slots 1A5 and 1A11</u>		
	SIM	ON	_____
	TM	ON	_____
	TE	ON	_____
	TMT	ON	_____
	RADDs OUT	ON	_____
	AIR	OFF	_____
	SUR	OFF	_____
	<u>d) TARGET Slots 1A6 and 1A12</u>		
	SIM	ON	_____
	TM	ON	_____
	TE	ON	_____
	TMT	ON	_____
	LIVE IN	OFF	_____
	LAND IN	OFF	_____
	TARG OUT	OFF	_____

SHIP HULL NO.

TEST CONDUCTOR  
SIGNATUREGOVERNMENT WITNESS  
SIGNATURE

DATE

---

**TEST DATA RECORDING**


---

<b><u>STEP</u></b>	<b><u>TEST ELEMENT</u></b>	<b><u>EXPECTED RESULTS</u></b>	<b><u>ACTUAL RESULTS</u></b>
20	<u>SM-902/U VSS CIRCUIT CARD FRONT PANEL LEDs</u> e) <u>IFF Slots 1A7 and 1A13</u> SIM TM TE TMT MTC IN TR IN MTC OUT TR OUT	ON ON ON ON OFF OFF OFF OFF	        
23	<u>RD-670/U RADCOR INDICATOR IS LIT ON PDU</u> RADCOR PDU switch	Indicator is Lit	 
24	<u>RD-670/U RADCOR WITNESS INDICATOR/DISPLAY</u> Power Health INPUT Health OUTPUT DSQM LCD Display	Indicator Lit Green Indicator Lit Red Indicator Lit Green Displays "TRIGGER INPUT SLOT 7 FAILED"	    
26	<u>RD-670/U RADCOR RECORDER INDICATORS ARE LIT</u> RADCOR EJECT button RADCOR AUDIO LEVEL meters RADCOR Time display	Button is Lit Meters are Lit Time Display is Lit	   
27	<u>SWITCHER INDICATOR IS LIT ON PDU</u> SWITCHER PDU switch	Indicator is Lit	 
28	<u>SWITCHER POWER INDICATOR IS LIT</u> SWITCHER POWER LED	Indicator is Lit	 
29	<u>AUX INDICATOR IS LIT ON PDU</u> AUX PDU switch	Indicator is Lit	 

SHIP HULL NO.

TEST CONDUCTOR  
SIGNATUREGOVERNMENT WITNESS  
SIGNATURE

DATE

---

**TEST DATA RECORDING**


---

<b><u>STEP</u></b>	<b><u>TEST ELEMENT</u></b>	<b><u>EXPECTED RESULTS</u></b>	<b><u>ACTUAL RESULTS</u></b>
30	<u>AUX INDICATOR IS EXTINGUISHED ON PDU</u> AUX PDU switch	Indicator is OFF	_____
31	<u>UPS INDICATOR IS LIT ON PDU</u> UPS Power (CB1) circuit breaker	Indicator is Lit	_____
32	<u>INPUT POWER INDICATORS ARE LIT ON UPS</u> UPS INPUT POWER switch BATTERY CHARGE LEDS	OK Indicator is Lit Indicates 100%	_____ _____ %
33	<u>OUTPUT POWER OK INDICATOR IS LIT ON UPS</u> UPS OUTPUT POWER switch	OK Indicator is Lit	_____
38	<u>CD-135/U Controller 748I COMPUTER POWER INDICATOR IS LIT</u> 748I Computer Power switch	Indicator is Lit	_____
39	<u>SYSTEM INITIALIZATION ON HMI DRAWER DISPLAY</u> Initializing System Starting networking Starting System Functions Starting Diagnostics Starting Auditing	OK OK OK OK OK	_____ _____ _____ _____ _____

SHIP HULL NO.

TEST CONDUCTOR  
SIGNATUREGOVERNMENT WITNESS  
SIGNATURE

DATE

---

**TEST DATA RECORDING**


---

**EQUIPMENT UNDER TEST**

<b><u>EQUIPMENT</u></b>	<b><u>SERIAL NO.</u></b>
SB-4229A(V)11/SP RSDS	_____
MT-7085/U Rack	_____
CD-135/U Controller	_____
SM-902/U VSS	_____
RD-670/U RADCOR	_____

**PREREQUISITES**

32011-2-001 Power Distribution System Insulation Resistance Test

**NOTE**

Write "N/A" in ACTUAL RESULTS spaces for test sections where optional equipment is not present in the SB-4229A(V)11/SP RSDS under test.

**TEST DATA RECORDING**

<b><u>STEP</u></b>	<b><u>TEST ELEMENT</u></b>	<b><u>EXPECTED RESULTS</u></b>	<b><u>ACTUAL RESULTS</u></b>
42	Repeat of steps on second SB-4229A(V)11/SP RSDS Rack		
3	J199 <u>CONTACT</u>		
	A to C	105 VAC to 125 VAC	_____ VAC
	B to Chassis Ground	< 1 VAC	_____ VAC
	A to C	≥50 to ≤63 Hz	_____ Hz
7	<u>PDU's SWITCHBOARD INDICATOR IS LIT</u> SWITCH BD (CB2) circuit breaker	Indicator is Lit	_____
8 (a)	<u>MASTER CONTROL PANEL'S INDICATOR IS LIT</u> AC PWR switch and DC PWR indicator is lit for Upper chassis AC PWR switch and DC PWR indicator is lit for Lower chassis		_____ _____

SHIP HULL NO.

TEST CONDUCTOR  
SIGNATUREGOVERNMENT WITNESS  
SIGNATURE

DATE



---

**TEST DATA RECORDING**


---

<b><u>STEP</u></b>	<b><u>TEST ELEMENT</u></b>	<b><u>EXPECTED RESULTS</u></b>	<b><u>ACTUAL RESULTS</u></b>
11	<u>POWER SUPPLY TEST POINT VOLTAGES</u>		
	<u>PS1 for Upper chassis</u>		
	+5V	+4.87 VDC to +5.39 VDC	_____ VDC
	-5V	-4.87 VDC to -5.39 VDC	_____ VDC
	+15V	+13.24 VDC to +14.64 VDC	_____ VDC
	-15V	-13.24 VDC to -14.64 VDC	_____ VDC
	<u>PS1 for Lower chassis</u>		
	+5V	+4.87 VDC to +5.39 VDC	_____ VDC
	-5V	-4.87 VDC to -5.39 VDC	_____ VDC
	+15V	+13.24 VDC to +14.64 VDC	_____ VDC
	-15V	-13.24 VDC to -14.64 VDC	_____ VDC
12	<u>POWER SUPPLY TEST POINT VOLTAGES</u>		
	<u>PS2 for Upper chassis</u>		
	+5V	+4.87 VDC to +5.39 VDC	_____ VDC
	-5V	-4.87 VDC to -5.39 VDC	_____ VDC
	+15V	+13.24 VDC to +14.64 VDC	_____ VDC
	-15V	-13.24 VDC to -14.64 VDC	_____ VDC
	<u>PS2 for Lower chassis</u>		
	+5V	+4.87 VDC to +5.39 VDC	_____ VDC
	-5V	-4.87 VDC to -5.39 VDC	_____ VDC
	+15V	+13.24 VDC to +14.64 VDC	_____ VDC
	-15V	-13.24 VDC to -14.64 VDC	_____ VDC
14	<u>MAIN POWER PDU INDICATOR IS LIT</u>		
	MAIN POWER (CB3) circuit breaker	Indicator is Lit	_____
15	<u>FAN POWER PDU INDICATOR IS LIT AND FANS ROTATE</u>		
	MAIN POWER (CB3) circuit breaker	Fans Indicator is Lit	_____
		Fans Rotate	_____
16	<u>VSS INDICATOR IS LIT ON PDU</u>		
	VSS PDU switch	Indicator is Lit	_____
<hr/>			
SHIP HULL NO.	TEST CONDUCTOR SIGNATURE	GOVERNMENT WITNESS SIGNATURE	DATE
<hr/>			

---

**TEST DATA RECORDING**


---

<b><u>STEP</u></b>	<b><u>TEST ELEMENT</u></b>	<b><u>EXPECTED RESULTS</u></b>	<b><u>ACTUAL RESULTS</u></b>
19	<u>SM-902/U VSS POWER INDICATOR IS LIT</u> SM-902/U VSS AC POWER switch	Indicator is Lit	_____
20	<u>SM-902/U VSS CIRCUIT CARD FRONT PANEL LEDs</u>		
	<u>a) Slot 1A1</u>		
	P-FAIL	ON (Green)	_____
	B-BUSY	OFF	_____
	BERR	OFF	_____
	<u>b) Slot 1A2</u>		
	RUN	ON (Green)	_____
	<u>c) RADDs Slots 1A5 and 1A11</u>		
	SIM	ON	_____
	TM	ON	_____
	TE	ON	_____
	TMT	ON	_____
	RADDs OUT	ON	_____
	AIR	OFF	_____
	SUR	OFF	_____
	<u>d) TARGET Slots 1A6 and 1A12</u>		
	SIM	ON	_____
	TM	ON	_____
	TE	ON	_____
	TMT	ON	_____
	LIVE IN	OFF	_____
	LAND IN	OFF	_____
	TARG OUT	OFF	_____

SHIP HULL NO.

TEST CONDUCTOR  
SIGNATUREGOVERNMENT WITNESS  
SIGNATURE

DATE



---

**TEST DATA RECORDING**


---

<b><u>STEP</u></b>	<b><u>TEST ELEMENT</u></b>	<b><u>EXPECTED RESULTS</u></b>	<b><u>ACTUAL RESULTS</u></b>
20	<u>SM-902/U VSS CIRCUIT CARD FRONT PANEL LEDs</u> e) <u>IFF Slots 1A7 and 1A13</u> SIM TM TE TMT MTC IN TR IN MTC OUT TR OUT	ON ON ON ON OFF OFF OFF OFF	        
23	<u>RD-670/U RADCOR INDICATOR IS LIT ON PDU</u> RADCOR PDU switch	Indicator is Lit	 
24	<u>RD-670/U RADCOR WITNESS INDICATOR/DISPLAY</u> Power Health INPUT Health OUTPUT DSQM LCD Display	Indicator Lit Green Indicator Lit Red Indicator Lit Green Displays "TRIGGER INPUT SLOT 7 FAILED"	    
26	<u>RD-670/U RADCOR RECORDER INDICATORS ARE LIT</u> RADCOR EJECT button RADCOR AUDIO LEVEL meters RADCOR Time display	Button is Lit Meters are Lit Time Display is Lit	   
27	<u>SWITCHER INDICATOR IS LIT ON PDU</u> SWITCHER PDU switch	Indicator is Lit	 
28	<u>SWITCHER POWER INDICATOR IS LIT</u> SWITCHER POWER LED	Indicator is Lit	 
29	<u>AUX INDICATOR IS LIT ON PDU</u> AUX PDU switch	Indicator is Lit	 

SHIP HULL NO.

TEST CONDUCTOR  
SIGNATUREGOVERNMENT WITNESS  
SIGNATURE

DATE

---

**TEST DATA RECORDING**


---

<b><u>STEP</u></b>	<b><u>TEST ELEMENT</u></b>	<b><u>EXPECTED RESULTS</u></b>	<b><u>ACTUAL RESULTS</u></b>
30	<u>AUX INDICATOR IS EXTINGUISHED ON PDU</u> AUX PDU switch	Indicator is OFF	_____
31	<u>UPS INDICATOR IS LIT ON PDU</u> UPS Power (CB1) circuit breaker	Indicator is Lit	_____
32	<u>INPUT POWER INDICATORS ARE LIT ON UPS</u> UPS INPUT POWER switch BATTERY CHARGE LEDS	OK Indicator is Lit Indicates 100%	_____ _____ %
33	<u>OUTPUT POWER OK INDICATOR IS LIT ON UPS</u> UPS OUTPUT POWER switch	OK Indicator is Lit	_____
38	<u>CD-135/U Controller 748I COMPUTER POWER INDICATOR IS LIT</u> 748I Computer Power switch	Indicator is Lit	_____
39	<u>SYSTEM INITIALIZATION ON HMI DRAWER DISPLAY</u> Initializing System Starting networking Starting System Functions Starting Diagnostics Starting Auditing	OK OK OK OK OK	_____ _____ _____ _____ _____

SHIP HULL NO.

TEST CONDUCTOR  
SIGNATUREGOVERNMENT WITNESS  
SIGNATURE

DATE

**TEST TITLE:** AN/SPQ-14 ASDS RACK ILO (LHD 7)

**TEST NO.:** 45011-3-062

**REV/CHG:** B

---

**TEST EQUIPMENT USED**

---

List all test equipment utilized in the test including all general and specialized test equipment, special test cables, attenuators, and any other materials requiring calibration. Include extra sheets as necessary to identify all test equipment.

<u>GENERIC NAME</u>	<u>MODEL</u>	<u>SERIAL NO.</u>	<u>CALIBRATION DUE DATE</u>	<u>REMARKS</u>
---------------------	--------------	-----------------------	---------------------------------	----------------

---

SHIP HULL NO.

TEST CONDUCTOR  
SIGNATURE

GOVERNMENT WITNESS  
SIGNATURE

DATE

---

---

**COMMENTS**

---

This sheet is provided for the test conductor or Government witness to make appropriate comments including the following:

- a. Visual observations of dynamic responses;
- b. Erratic or unusual equipment behavior;
- c. Operational or handling difficulties;
- d. Procedural corrections;
- e. Equipment malfunctions;
- f. Discrepancies noted during test conduct; and,
- g. Waivers including reference to authorization document, i.e., letter, message, etc.

Indicate if a Test Problem Report (TPR) was generated with respect to these or other problems.

---

**SHIP HULL NO.**

---

**TEST CONDUCTOR  
SIGNATURE**

---

**GOVERNMENT WITNESS  
SIGNATURE**

---

**DATE**

---