Approved by: ______TDD Organization and Code

TEST NO: 45011-5-055

REV/CHG: A

Date: _____

COVER S	SHEET
---------	-------

TEST PROCE	DURE PREPARATION:	
Prepared by:	NSWC PHD DAM NECK DET CODE 6E10 TDA Organization and Code	Date: <u>1 DEC 98</u>
TEST PROCEI	DURE REVIEW:	
Reviewed by:	NSWC PHD DAM NECK DET CODE 6D10 TDM Organization and Code	Date: 4 JAN 99
DOCUMENTA'	TION CERTIFICATION:	

TEST NO: 45011-5-055 REV/CHG: A

REVISION RECORD

		Арр	roval
REV/CHG	DESCRIPTION	<u>INITIAL</u>	DATE
-	Original Issue	NSWC	10 JAN 98
Α	Incorporated validation changes.	FES	18 DEC 98

LIST OF EFFECTIVE PAGES

| PG-REV |
|--------|--------|--------|--------|--------|--------|--------|
| 1 - A | 2 - A | 3 - A | 4 - A | 5 - A | 6 - A | 7 - A |
| 8 - A | 9 - A | 10 - A | 11 - A | 12 - A | 13 - A | 14 - A |
| 15 - A | 16 - A | 17 - A | 18 - A | 19 - A | | |

CONVERTER OPERABILITY

TEST OUTLINE

1. OBJECTIVE:

To verify that the CV-3989(V)1/SP Dual Signal Data Converter (CV-3989(V)1/SP DSDC) is operating properly with interfacing equipment.

REV/CHG: A

2. ESTIMATED TESTING TIME:

1.5 hours

3. <u>REFERENCES</u>:

SE650-AQ-MMO-A10, Technical Manual, Operations and Maintenance for the Dual Signal Data Converter, CV-3989(V)1/SP

4. TEST OR SUPPORT EQUIPMENT AND MATERIAL:

GENERIC NAME	<u>QUANTITY</u>	IDENTIFYING INFORMATION
a. Multimeterb. Oscilloscopec. Terminator, 75-Ohms	1 1 1	SCAT 4245 or equivalent SCAT 4308 or equivalent SCAT 4596 or equivalent
d. T-Connector	1	UG-1173/u or UG-107B/u BNC

5. COMPUTER PROGRAMS REQUIRED:

None

6. PREREQUISITES:

45011-3-060, CV-3989(V)1/SP Analog to Digital Converter ILO

7. SPECIAL CONDITIONS AND SERVICES:

115 VAC, 1 φ, 60 Hz Power

8. EQUIPMENT INVOLVED IN TEST:

- a. CV-3989(V)1/SP DSDC
- b. Normal radar outputs applicable to ship configuration
- c. Normal navigation outputs applicable to ship configuration

9. CONFIGURATION:

No field changes required to run this test.

CONVERTER OPERABILITY

TEST OUTLINE

10. <u>METHOD</u>:

Utilizing inputs from the radar (Antenna Azimuth, True Bearing Indication (Lb), Master Trigger (Tm), and navigation (CQO and Distance/Speed), verify presence of the Radar Display and Distribution System (RADDS) Data Stream at each of the eight CV-3989(V)1/SP DSDC RADDS outputs.

REV/CHG: A

11. <u>STATION ASSIGNMENTS</u>:

STATION NO. PERSONNEL COMMENTS

CV-3989(V)1/SP DSDC 1 Electronic Technician Performs Operability Test

CONVERTER OPERABILITY REV/CHG: A

SAFETY INSTRUCTIONS

a. Test personnel will strictly adhere to all safety precautions including, but not limited to, all Caution and Warning notes contained in this test procedure and applicable documents.

- b. Comply with ships regulations and safety precautions prior to antenna rotation and radiation. Remain clear of swing radius of rotating antennas.
- c. The operation of this equipment involves the use of high voltages that are dangerous to life. Extreme caution must be exercised at all times. Do not work on open or disassembled units when power is applied.

INITIAL CONDITIONS AND SETUP

TEST NO: 45011-5-055

	STEP	STATION	INSTRUCTIONS
	1	Radar	Ensure proper radar inputs are being supplied such as 5 wire Azimuth, True Bearing indication (Lb), and Master Trigger (Tm).
	2	Navigation	Ensure proper navigation inputs are being supplied in accordance with ship configuration as follows:
	Ship		
<u>Input</u>	<u>Paran</u>	<u>neter</u>	Requirement
CQO	90° (E	ast)	Course 5 Wire Synchro (360° Per revolution) 115 VAC, 60 or 400 Hz, 1 ϕ , equal 90° Synchro input.
Distance (Traveled) or			Distance 5 Wire Synchro (360 ⁰ revolutions per 2000 yards of travel) 115 VAC, 60 or 400 Hz, 1 φ, equal 60 revolution per minute.
Ships Velocity	10 Kn	ots	Speed 5 Wire Synchro (40 Knots per revolution) 115 VAC, 60 or 400 Hz, 1 φ
	3	CV-3989(V)1/SP DSDC	Turn Maintenance Disconnect switch to OFF position (2JR Type).
	4	CV-3989(V)1/SP DSDC	Open hinged door and set Upper and Lower chassis 1A2 Power Supply module switches to OFF position.
	5	CV-3989(V)1/SP DSDC	Set AC POWER switch to OFF position.
	6	CV-3989(V)1/SP DSDC	Disconnect RADAR 1 input cable connected to TM1 (J1).
	7	CV-3989(V)1/SP DSDC	Using Oscilloscope, ensure radar input signal is present at disconnected cable. Input level should be a trigger pulse of positive polarity and 20V ±5V amplitude. The pulse duration should be 1 µs to 10 µs at a frequency equal to Pulse Repetition Frequency (PRF) of the radar.

TEST TITLE: CV-3989(V)1/SP ANALOG TO DIGITAL

CONVERTER OPERABILITY

INITIAL CONDITIONS AND SETUP

TEST NO: 45011-5-055

REV/CHG: A

STEP STATION INSTRUCTIONS 8 CV-3989(V)1/SP DSDC Reconnect radar input cable to TM1 (J1). 9 Repeat steps 6 through 8 for RADAR 2 input cable to TM1 (J17). 10 CV-3989(V)1/SP DSDC Disconnect input cable connected to SYNCHRO T/R (J49). NOTE The input cable connected to J49 provides the radar antenna azimuth, true bearing, and ship's navigation information (CQO and Distance/Speed). 11 Turn Maintenance Disconnect switch to ON CV-3989(V)1/SP DSDC position. 12 CV-3989(V)1/SP DSDC Using a Multimeter, ensure radar 5 wire antenna azimuth input signals are present at disconnected cable. Input should be as follows: 115 VAC, 60 or 400 Hz, 1 o, 5 Wire Synchro information on R1 and R2 and 0 VAC to 90 VAC on any of the S1, S2, and S3 leads. J49 Cable Pin Signal 10 Azimuth1 R1 (R HI) 11 Azimuth1 R2 (R LO) 12 Azimuth1 S1 → Varying Amplitude 13 Azimuth1 S2 → Varying Amplitude Azimuth1 S3 → Varying Amplitude 14 29 Azimuth2 R1 (R HI) 30 Azimuth2 R2 (R LO) 31 Azimuth2 S1 → Varying Amplitude 32 Azimuth2 S2 → Varying Amplitude Azimuth2 S3 → Varying Amplitude 33 13 CV-3989(V)1/SP DSDC Using a Multimeter, ensure CQO 5 wire navigation information is present at disconnected cable. Input should be as follows: 115 VAC, 60 or 400 Hz, 1 o, 5 Wire Synchro information on R1 and R2 and 0 VAC to 90 VAC on any two of the S1, S2, and S3 leads.

INITIAL CONDITIONS AND SETUP

TEST NO: 45011-5-055

<u>STEP</u>	STATION		INSTRUCTIONS
		5 (C) 6 (C) 7 (C) 8 (C) 8	Signal CQO R1 (R HI) CQO R2 (R LO) CQO S1 → Varying Amplitude CQO S2 → Varying Amplitude CQO S3 → Varying Amplitude
14	CV-3989(V)1/SP DSDC	5 wire naviga disconnected follows: 115 Synchro info	imeter, ensure Distance/Speed ation information is present at d cable. Input should be as VAC, 60 or 400 Hz, 1 φ, 5 Wire rmation on R1 and R2 and 0 AC on any two of the S1, S2, s.
		18 D 19 D 20 D	ignal ist/Speed R1 (R HI) ist/Speed R2 (R LO) ist/Speed S1 → Varying Amplitude ist/Speed S2 → Varying Amplitude ist/Speed S3 → Varying Amplitude
15	CV-3989(V)1/SP DSDC	bearing input	imeter, ensure radar true t signals are present at d cable. Input should be as
		J49 Cable Pin 34	Signal True Bearing 6.3 VAC, 60 Hz (Radar 1 is providing true azimuth 1 information) or 0.5 VAC, 60 Hz (Radar 1 is providing relative azimuth 1 information)
		35	True Bearing RTN
		36	True Bearing 6.3 VAC, 60 Hz (Radar 2 is providing true azimuth 2 information)

TEST TITLE: CV-3989(V)1/SP ANALOG TO DIGITAL CONVERTER OPERABILITY **TEST NO:** 45011-5-055

INITIAL CONDITIONS AND SETUP

<u>STEP</u>	STATION		INSTRUCTIONS
		<u>J49</u> <u>Cable Pin</u>	Signal or 0.5 VAC, 60 Hz (Radar 2 is providing relative azimuth 2 information)
		37	True Bearing RTN
16	CV-3989(V)1/SP DSDC	Turn Mainter OFF position	nance Disconnect switch to n.
17	CV-3989(V)1/SP DSDC	Reconnect in SYNCHRO	nput cable disconnected from T/R (J49).

TESTING STEPS

TEST NO: 45011-5-055

STEP	STATION	INSTRUCTIONS
<u>LIGH</u>	<u>r off</u>	
1	CV-3989(V)1/SP DSDC	Turn Maintenance Disconnect switch to ON position.
2	CV-3989(V)1/SP DSDC	Set AC POWER switch to ON position.
3	CV-3989(V)1/SP DSDC	Verify Power ON indicator is lit.
4	CV-3989(V)1/SP DSDC	Set Upper and Lower chassis 1A2 Power Supply module switches to ON position.
5	CV-3989(V)1/SP DSDC	Verify 1A2 Power Supply modules +5V, +12V and -12V indicators are lit on both the Upper and Lower chassis.
RADE	OS OUTPUT TEST	
6	CV-3989(V)1/SP DSDC	Ensure the Light Emitting Diode (LED) indicator states for the Formatter module (1A3):
		ModuleIndicatorStateFormatterPSL (Amber LED)ON(1A3)RUN (Green LED)ONRECORDon Test Data Recording sheet.
7	CV-3989(V)1/SP DSDC	The Synchro module (1A4) Status LED indicates presence of Synchro inputs. Ensure either of the following indicator states for the Synchro Module:
		a. (Any Synchro Input NOT present) Module Indicator State Synchro Status (Red LED) ON (1A4) BUS Error (Red LED) OFF
		b. (All Synchro Inputs present) Module Indicator State Synchro Status (Red LED) OFF (1A4) BUS Error (Red LED) OFF RECORD on Test Data Recording sheet.

REV/CHG: A

TEST NO: 45011-5-055

TESTING STEPS

STEP	STATION	<u>II</u>	<u>NSTRUCTIONS</u>
8	CV-3989(V)1/SP DSDC	Status LEDs in Triggers and R	modules (1A5) CH1 and CH2 dicate presence of RADAR ADDS Data Stream outputs. owing indicator states for modules:
		Module Serializer (1A5) CH1 and CH2	Indicator a. (TM1 NOT Present) AIR (Green LED) OFF SUR (Green LED) OFF TM1 (Green LED) OFF TM2 (Green LED) OFF
			b. (TM1 Present) AIR (Green LED) ON SUR (Green LED) ON TM1 (Green LED) ON TM2 (Green LED) ON
			c. (TE NOT Present) TE (Green LED) OFF
			d. (TE Present) TE (Green LED) ON
			e. (TIFF NOT Present) TIFF (Green LED) OFF
		RECORD on T	f. (TIFF Present) TIFF (Green LED) ON Test Data Recording sheet.
9	CV-3989(V)1/SP DSDC		nuth II module (1A15) CH1 s LEDs indicate presence of nuth inputs.
		Valid Stabilized SIN/COS ACP/ARP SDT 3 Wire 6 Wire	d Azimuth Inputs

CONVERTER OPERABILITY

REV/CHG: A

TESTING STEPS

STEP STATION

INSTRUCTIONS

TEST NO: 45011-5-055

Ensure the following indicator states for the Quad Azimuth II module if installed.

a. (Stabilized Azimuth NOT present)

Module	Indicator	State
Quad	CH1 (Green LED)	OFF
Azimuth II	CH2 (Green LED)	OFF
(1A15)	,	

b. (Stabilized Azimuth present)

<u>Module</u>	<u>Indicator</u>	<u>State</u>
Quad	CH1 (Green LED)	ON
Azimuth II	CH2 (Green LED)	ON
(1A15)		

RECORD on Test Data Recording sheet.

10 CV-3989(V)1/SP DSDC Connect oscilloscope and T-Connector to output AIR A (J3) of CV-3989(V)1/SP DSDC.

NOTE

Connect a 75-ohm resistive load across CV-3989(V)1/SP DSDC output T-Connector before connecting oscilloscope for measurements. The 75-ohm load simulates actual equipment loading.

RADDS OUTPUT

11 CV-3989(V)1/SP DSDC Monitor output signal at AIR A jack (J3). RECORD on Test Data Recording sheet. Expected output signal is shown in Figure 1.




Figure 1. RADDS Data Stream.

CONVERTER OPERABILITY

TESTING STEPS

REV/CHG: A

STEP STATION INSTRUCTIONS NOTE: Data burst shown in Figure 1 is repeated at the PRF of the radar. The 128us "data bit" region shown in Figure 1 contains 64 data bits. Step 11 tests only for the presence of the 64 data bits, NOT for the condition of each bit (High or Low). 12 Repeat steps 10 and 11 for the following output jacks: a. SUR A (J4) b. AIR B (J11) c. SUR B (J12) d. AIR A (J19) e. SUR A (J20) f. AIR B (J27) g. SUR B (J28) RECORD on Test Data Recording sheet. 13 Disconnect oscilloscope from output SUR B CV-3989(V)1/SP DSDC (J28).

SHUTDOWN AND SECURING

STEP	STATION	INSTRUCTIONS
1	CV-3989(V)1/SP DSDC	Set Upper and Lower chassis 1A2 Power Supply module switches to OFF independently.
2	CV-3989(V)1/SP DSDC	Set AC POWER switch to OFF position.
3	CV-3989(V)1/SP DSDC	Turn Maintenance Disconnect switch to the OFF position.

TEST NO: 45011-5-055

TEST NO: 45011-5-055

REV/CHG: A

TEST DATA RECORDING

EQUIPMENT UNDER TEST							
		EQUIPMENT CV-3989(V)1/SP DS	SDC <u>SERIAL I</u>	<u>NO</u> .			
<u>PREREQUISITES</u>							
45011-3-060, CV-3989(V)1/SP Analog to Digital Converter ILO							
Prerequisites Completed Signature and Date							
TEST DATA RECORDING							
STEP	TEST ELE	MENT	EXPECTED RESULTS	ACTUAL RESULTS			
6	FORMATT PSL RUN	ER MODULE (1A3) FR	ONT PANEL LEDs ON (Amber) ON (Green)				
7) MODULE (1A4) FRON Inchro Input NOT Preser					
	b. All Syn Status BUS E	chro Inputs Present rror	OFF OFF				
8		ER MODULE (1A5) CH1 OT Present	OFF OFF OFF OFF				
	b. TM1 Pi AIR SUR TM1 TM2	<u>resent</u>	ON (Green) ON (Green) ON (Green) ON (Green)				
HIP HULL NO. TEST CONDUCTOR GOVERNMENT WITNESS DATE							

SIGNATURE

SIGNATURE

TEST DATA RECORDING

TEST NO: 45011-5-055

STEP TEST ELE	<u>EMENT</u>	EXPECTED RESULTS	ACTUAL RESULTS
c. <u>TE NC</u> TE	OT Present	OFF	
d. <u>TE Pre</u> TE	<u>esent</u>	ON (Green)	
e. <u>TIFF N</u> TIFF	NOT Present	OFF	
f. <u>TIFF F</u> TIFF	<u>Present</u>	ON (Green)	
SERIALIZER MODULE (1A5) CH2 FRONT PANEL LEDs			
a. <u>TM1 N</u> AIR SUR TM1 TM2	IOT Present	OFF OFF OFF	
b. <u>TM1 P</u> AIR SUR TM1 TM2	<u>Present</u>	ON (Green) ON (Green) ON (Green) ON (Green)	
c. <u>TE NC</u> TE	OT Present	OFF	
d. <u>TE Pre</u> TE	esent	ON (Green)	
e. <u>TIFF N</u> TIFF	NOT Present	OFF	
f. <u>TIFF F</u> TIFF	<u>Present</u>	ON (Green)	
SHIP HULL NO.	TEST CONDUCTOR SIGNATURE	GOVERNMENT WITNESS SIGNATURE	DATE

TEST NO: 45011-5-055

REV/CHG: A

TEST DATA RECORDING

STEP 1	TEST ELEMENT	EXPECTED RESULTS	ACTUAL RESULTS
	QUAD AZIMUTH II MODULE (1A15) FF a. <u>Stabilized Azimuth NOT Present</u> CH1 CH2	OFF OFF	
I	b. <u>Stabilized Azimuth Present</u> CH1 CH2	ON (Green) ON (Green)	
	OUTPUT SIGNAL AIR A (J3)	As shown in Figure 1	
1	OUTPUT SIGNAL a. SUR A (J4) b. AIR B (J11) c. SUR B (J12)	As shown in Figure 1 As shown in Figure 1 As shown in	
•	d. AIR A (J19) e. SUR A (J20) f. AIR B (J27)	Figure 1 As shown in Figure 1	
	g. SUR B (J28)		
SHIP HUL	L NO. TEST CONDUCTOR GO	OVERNMENT WITNESS SIGNATURE	DATE

TEST TITLE: CV-3989(V)1/SP ANALOG TO DIGITAL

CONVERTER OPERABILITY

TEST EQUIPMENT USED

TEST NO: 45011-5-055

REV/CHG: A

List all test equipment utilized in the test including all general and specialized test equipment, special test cables, attenuators, and any other materials requiring calibration. Include extra sheets as necessary to identify all test equipment.

SERIAL CALIBRATION

GENERIC NAME MODEL NO. DUE DATE REMARKS

SHIP HULL NO. TEST CONDUCTOR GOVERNMENT WITNESS DATE SIGNATURE SIGNATURE

TEST TITLE: CV-3989(V)1/SP ANALOG TO DIGITAL CONVERTER OPERABILITY

TEST NO: 45011-5-055

REV/CHG: A

COMMENTS

This sheet is provided for the test conductor or Government witness to make appropriate comments including the following:

- a. Visual observations of dynamic responses;
- b. Erratic or unusual equipment behavior;
- c. Operational or handling difficulties;
- d. Procedural corrections;
- e. Equipment malfunctions;
- f. Discrepancies noted during test conduct; and,
- g. Waivers including reference to authorization document, i.e., letter, message, etc.

Indicate if a Test Problem Report (TPR) was generated with respect to these or other problems.

SHIP HULL NO. TEST CONDUCTOR GOVERNMENT WITNESS DATE SIGNATURE SIGNATURE